is outstanding as due to the party whose wereabouts are not known. It is therefore hereby notified that if the amount is not claimed (by presenting a bill to this office for the refund of amount) within two months from this date, the same will be credited to Government.

K. PONNAPPA,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 6th December 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 4th January 1919, for restoring Kalgere Minor Tank, Registered No. 60 of Chitaldrug Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kalgere Minor Tank, Registered No. 60, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Chitaldrug Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for Restoring Kalgere Tank, Registered No. 60 of Bharmasagara Hobli, Chitaldrug Taluk.

Item No.	Particulars	Per	Quantity
	Bund.		
1	Earthwork excavation and forming including lead watering and tamping, etc., works complete.	C. yd.	5,994
2	Forming grips, removing top soil strengthening breached portion, filling up scours, etc., complete.	Lump	sum Rs.
3	Gravel backing to revetment	C. yd.	585
4	Resetting old stone revetment with new jelly including lead, etc., complete...	"	1,115
5	Do new stone work	"	600
	Waste weir.		
6	Dismantling existing wall, etc.	C. ft.	250
7	Earthwork excavation	C. yd.	63
8	Concrete in surki mortar	C. ft.	488
9	Pointing in surki mortar	Sq.	18·04
10	Burnt stone in surki mortar	C. ft.	1,497
11	Burnt stone coping slabs over body wall including dressing, Chamfering the edges and lead jointing, etc.	S. ft.	348
	Wings.		
12	Rough stone work, old, resetting, etc.	C. yd.	40
13	New stone work with jelly and gravel backing	"	40
	Apron.		
14	Earthwork excavation using the earth to wings	C. yd.	110
15	New stone work with jelly and wedging	"	112
16	Burnt stone slabs 6" dressed	S. ft.	530
	Sluice.		
17	Cutting open the bund, examining and closing the leakages and building pucca cisterns, etc	Lump	sum Rs.
18	Clearing site and baling out water...	Lump	sum Rs.
	Sundries.		
19	Clearing jungle with roots, etc.	Lump	sum Rs.
20	Resetting old grade stones with new bed slabs to stand and level including cutting figures, numbering and painting, etc.	Each	20
21	Providing new grade stones complete, with bed slabs	"	13
22	Providing top width stones	"	33
23	Do gauge stones	"	3
24	Do register number stone	"	1
25	Do bench mark stones	"	2
26	Do date and year stone	"	1

Notification dated Camp Hanagal, 12th December 1918.

The public and others who are in need of employment due to unfavourable seasonal conditions may approach the Public Works Sub-Divisional Officers concerned for work. The following are the works in progress. (A statement is attached).

Statement showing the Major Works in Progress in the Division arranged Talukwar.—

No.	Name of work	Amount of estimate	Outlay to end of June 1916	Grant for 1918-19	Outlay during 1918-19 to end of September 1918	Remarks
1	2	3	4	5	6	7
	Chitaldrug Taluk.	Rs.	Rs.	Rs.	Rs.	*Headquarter of Sub-Division Office.*
1	Improving Bheemasamudra Tank Channels ...	7,015	6,909	...	...	Work is since completed, Chitaldrug Sub-Division Office.
2	Constructing a kitchen block to Government High School at Chitaldrug.	5,340	400	5,000	...	
3	Constructing Police Station and lines at Bharmasagara.	8,325	400	2,000	...	
	Hiriyur Taluk.					
4	Extending the Anglo-Vernacular School at Hiriyur.	4,530	1,277	1,000	223	Do
	Challakere Taluk.					
5	Constructing Police Station and lines at Sanikere.	7,060	339	2,000	202	Challakere Sub-Division Office, in progress.
6	Constructing a combined Dispensary at Challakere.	8,330	750	2,000	4	
	Molakalmuru Taluk.					
7	Restoring Chikanahally tank	7,790	7,112	...	25	
8	Closing the breach in the bund of Chikanahalli tank.	3,800	765	...	350	
9	Improving Herekerehalli tank	14,821	12,942	...	...	
10	Constructing Anglo-Vernacular School at Molakalmuru.	8,600	500	3,000	...	
	Davangere Taluk.					
11	Restoring Thumbagere tank	3,359	3,052	...	51	Davanagere Sub-Division Office
12	Constructing Police Station and lines at Anaji	7,875	206	2,000	...	
	Jagalur Taluk.					
13	Extending the Anglo-Vernacular School at Jagalur.	2,587	...	...	146	
14	Constructing Police Station and lines—Gadimakunta.	8,055	76	2,000	...	
	Holalkere Taluk.					
15	Restoring Sadarahally Herekere tank and Arasinaghatta, Chickakere, Holalkere Taluk.	4,868	1,391	2,000	...	Holalkere Sub-Division Office.
16	Constructing V. E. School at Mutugadur ...	2,800	...	...	...	
	Hosadurga Taluk.					
17	Restoring Neeragunda tank	7,216	6,618	...	...	
18	Constructing a Police Station at Budihal ...	2,625	282	...	...	

N. G. KRISHNA IYENGAR
Executive Engineer.

BENKIPUR RANGE OFFICE.

Dated 11th December 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Temporary Engineer, Benkipur, up to 20th January 1919 for constructing an anicut across the river Bhadra, near Sidlipur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st January 1921.

2. The plans, detailed estimate and conditions may be seen at the Temporary Engineer's Office at Benkipur between the hours of 11 A.M. and 5 P.M., except on holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Temporary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.